



ADDENDUM #1

ISSUE DATE: **May 16, 2014**

Holders of Request for Bids # '14/37/B CIP # 646 – 2013 CIP Reallocation Municipal Facility Reroofing, Repairs and Related Work

The following Addendum shall be incorporated into the Bidding/Contract Documents for the above referenced project:

- 1) Fire Station #7: modify scope of work to include removal of existing BUR membrane, inspect, remove and replace any wet or damaged perlite tapered insulation areas with new perlite to match. Allow 20% replacement. Use high density ½" polyiso recovery board in lieu of ½ densdeck board.**
- 2) Marty Sanchez: Provide moisture scan of entire roof, remove membrane in any wet areas prior to re-roofing. Allow 10% additional removal area of membrane. Use high density ½" polyiso recovery board in lieu of ½ densdeck board.**
- 3) Courthouse: Patch, repair and paint any and all damaged areas of GWB ceiling areas below leaks in addition to replacing any and all damaged ceiling tiles.**
- 4) Clarification for FS#5, FS#7, Marty Sanchez: Scope of work calls for Heat Inducted Welded (Rinobond) 80mil PVC scrim reinforced membrane system and all related work.**

Please acknowledge receipt of this Addendum with the Bid.

Jason M. Kluck
City of Santa Fe, Public Works Department
Facilities Division Project Administrator
Ph. 955-5937

END: Addendum Number One (1).

