

Addendum No. 1 Santa Fe Trails Bus Shelters Ph 2 RFB '16/05/B

CIP Project #665A

November 2, 2015

This Addendum has just this 1 page

Addendum to the Request For Bids:

1. This Addendum forms a part of the Contract Documents and modifies the original Request For Bids issued October 16, 2015. Acknowledge receipt of this Addendum in the space provided on the Bid Form. All other provisions of the Request For Bids '16/05/B shall remain unchanged unless expressly noted herein.
2. Addendum shall be distributed to the pre-qualified bidders and to the plan rooms, via email. Recipients of this addendum shall confirm receipt of this issued addendum by email.

Entire Plan Set Clarification:

1. Anchoring hardware is defined as the hardware to be supplied by the Contractor that will be used later to secure the bus shelters to the concrete surfaces. Throughout the plan set, the anchoring hardware required for the three types of bus shelters shall be as follows:
 - a. Dent bolts (breakaway bolts) are only required for anchoring Product Package A, the stand-alone sign panel with feet. The set of part numbers required for each of the four anchor points are:
 - #6220M Dent bolt
 - #6231-2 Drop in anchor
 - #4002 Hex Head Nut
 - #6694 Square washerTherefore, for the base bid, two hundred forty four sets of the above listed parts will be provided to the Owner
 - b. 8 sets of Dent bolts shall be provided as spares to the Owner. A set is one each of the four part numbers listed in 1. above.
 - c. Product Package B and Product Package C will be anchored at all points by anchor bolts per ASTM F 1554, Grade 36 (spec section 2.1.C on page 05 10 00-3). These anchor bolts should be ½" x 10.5", all thread, zinc coated, with a ½" nut and a ½" washer.